Bruhat Bangalore Mahanagara Palike

Excecutive Engineer Yelahanka Project Division

Name of Work: Providing Basic Amenities and Procurement of Dustbins in Ward No.08,Kodigenahalli.

Schedule - B

Sl No	Quantity	Description of Item	Unit	Rate, Rs	
				In Figures	In Words
1	4.00	Supplying ,installation ,Commissioning and Testing CP PLUS 2 MP PTZ 1/2.8" 2MP Exmor R CMOS Image sensor Max. 50/60fps@1080P, 25/30/50/60fps@720P,Powerful 25x Optical and 16x Digital zoom WDR(120dB), 3D DNR, Day/Night(ICR), BLC, HLC Up to 300 presets, 8 auto scan, 8 tour, 5 pattern, 8 auto pan IR Range of 150 Mtr. , IP66, Support PoE Plus inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	82962.00	Rupees Eighty Two Thousand Nine Hundred Sixty Two Only
2	75.00	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	23160.00	Rupees Twenty Three Thousand One Hundred Sixty Only
3	5.00	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	66892.00	Rupees Sixty Six Thousand Eight Hundred Ninety Two Only
4	3.00	Supplying ,installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	257420.00	Rupees Two Lakh(s) Fifty Seven Thousand Four Hundred Twenty Only
5	6.00	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	22850.00	Rupees Twenty Two Thousand Eight Hundred Fifty Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

No	Quantity	Description of Item	Unit	Rate, Rs	
				In Figures	In Words
6	4.00	Supplying ,installation ,Commissioning and Testing D-Link 24-Port Gigabit Switch With 4 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	35300.00	Rupees Thirty Five Thousand Three Hundred Only
7	34.00	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	28500.00	Rupees Twenty Eight Thousand Five Hundred Only
8	6.00	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	64250.00	Rupees Sixty Four Thousand Two Hundred Fifty Only
9	6.00	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	12200.00	Rupees Twelve Thousand Two Hundred Only
10	8754.85	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Mtr	165.00	Rupees One Hundred Sixty Five Only
11	25.00	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	22500.00	Rupees Twenty Two Thousand Five Hundred Only
12	25.00	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	9500.00	Rupees Nine Thousand Five Hundred Only
13	25.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	No	8500.00	Rupees Eight Thousand Five Hundred Only
14	12.00	Providing Internet charges connecting CCTV with IP Based for one month	No	3500.00	Rupees Three Thousand Five Hundred Only
15	75.00	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	6500.00	Rupees Six Thousand Five Hundred Only
16	25.00	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	2200.00	Rupees Two Thousand Two Hundred Only
17	1.00	Supplying ,installation ,Commissioning and Testing UPS 2 KVA with batteries Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	65400.00	Rupees Sixty Five Thousand Four Hundred Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

No	Quantity	Description of Item	Unit	Rate, Rs	
				In Figures	In Words
18	25.00	Erecting of pole .The pole shall be erected in cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	No	6400.00	Rupees Six Thousand Four Hundred Only
19	10.00	Providing and Fixing HDMI Cables 10 Mtrs inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	6500.00	Rupees Six Thousand Five Hundred Only
20	3.00	Supplying ,installation ,Commissioning and Testing Video Manager Application Software for Display and Management of Camera on Video Display Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	32500.00	Rupees Thirty Two Thousand Five Hundred Only
21	3.00	Supplying ,installation ,Commissioning and Testing of 43" LED TV - Reputed make Sony/samsung/LG inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	45000.00	Rupees Forty Five Thousand Only
22	100.00	Supplying ,installation ,Commissioning and Testing Patch cords CAT6 2 Mtr Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	1200.00	Rupees One Thousand Two Hundred Only
23	2.00	Supplying ,installation ,Commissioning and Testing Server rack 15u Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	34500.00	Rupees Thirty Four Thousand Five Hundred Only
24	84.00	Maintenance charges for one year for each camera	No	5500.00	Rupees Five Thousand Five Hundred Only
25	1.00	Supplying ,installation ,Commissioning and Testing of CPU - I 3 Processor - 450MHz, 8GB Ram, 250 Gb Hard Disk Full Core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	41564.00	Rupees Forty One Thousand Five Hundred Sixty Four Only
26	300.00	Supplying of dustbin for collection dry and wet waste for segreation , made up of plastic inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	960.00	Rupees Nine Hundred Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-56

Contractor